



OUTSIDE HEIGHT OF THE BOX "B" SHALL RANGE FROM 3' TO 6'  
 INSIDE HEIGHT OF THE BOX "A" SHALL RANGE FROM 2.5' TO 5.5'

**NOTES:**

1. USE 4,000 PSI CONCRETE AND PROVIDE FOR HS-20 LOADING.
2. PROVIDE LIFT HOLES OR PIN IN ACCORDANCE WITH OSHA STANDARDS.
3. SEAL JOINTS WITH FLEXIBLE BUTYL RUBBER BASE CONFORMING TO ASTM M-19B.
4. WAFFLE BOX SHALL HAVE A FOUNDATION OF 6" #57 STONE.
5. FOR DROP INLET FRAME AND GRATE, REFER TO DETAIL SW - 07.

SECTION: STORMWATER	24" X 36" PRECAST CONCRETE WAFFLE DROP INLET BOX WITH 4 KNOCKOUT PANELS	PUBLIC SERVICES DEPARTMENT
DATE: 2023		
DRAWN BY: JWP		
CHECKED BY: TOWN PSD		
SCALE: NOT TO SCALE		DETAIL NO. SW - 05